

**PREDICTION OF DEFORMATIONS IN POST-
TENSIONED PRESTRESSED SUSPENDED SLABS
IN TALL BUILDINGS**

Thomas J. Vincent
B.E. Civil Engineering (Hons.)

A thesis submitted in fulfilment
of the requirements for the degree of
Master of Engineering

at

The University of Adelaide
(Faculty of Engineering)

July 2008

APPENDICES

Appendices to the thesis submitted in fulfillment
of the requirements for the degree of
Master of Engineering, for

Thomas J. Vincent
B.E. Civil Engineering (Hons.)

at

The University of Adelaide
(Faculty of Engineering)

July 2008

APPENDIX A

Long Term Deflection Prediction Method Proposed by Hwang and Chang
(1996).

NOTE:

This appendix is included in the print copy of the
thesis held in the University of Adelaide Library.



APPENDIX B


Examples of modeling construction effect of propping and back propping by the use of load factors (k) from J.F.M.A. Prado et al (2003).

Examples of modeling construction effect of propping and back propping by the use of load factors (k) from J.F.M.A. Prado et al (2003).

Load factors (k) for floors and props (2 + 2 propping and back propping scheme)

Where; $k = \frac{\text{loading on the floor (or on the props)}}{\text{Self weight of the floor}}$






APPENDIX C


151 Pirie Structural Plans Incorporating Photos of Slab Details.


- Take note that the building was labelled as Admiral House during the design stages, the name change to 151 Pirie occurred after these plans were completed.

NOTE:

The structural plans (6 pages) in this appendix are included in the print copy of the thesis held in the University of Adelaide Library.











APPENDIX D

Concrete Mixtures and Slab Pour Details.

Slab pour details for R and D project on Admiral House

Date	Level	Pour	Product code	Docket number	Time	Truck #	Load size (m ³)	Temp (Deg C)	Slump (mm)	
					Btchd Smpld			conc	target actual	
11-May-05	1	South	N322F	7872	5.32				80 95	
20-May-05	1	North	N322F	7872	5.41	662	5.8	18	80 85	
30-May-05	2	South	N322F	7872	5.31	668		16	80 85	
6-Jun-05	2	North	N322F	7872	5.41	653		17	80 85	
17-Jun-05	3	South	N402F	7872	5.50	664	7.2	16	80 110	
25-Jun-05	3	North	N322F	7872	5.35	684	7.2	19	80 85	
6-Jul-05	4	South	N402F	7872	5.54		7.2	16	80 85	
13-Jul-05	4	North	N402F	7872	3.34	668	7.2	15	80 85	
22-Jul-05	5	South	N402F	7872			7.2		80	
27-Jul-05	5	Pour missed due to programming and placing thermocouples								
5-Aug-05	6	Pour missed due to programming and placing thermocouples								
10-Aug-05	6	North	N402F	7872	3.38	684	7.2	15	90 85	
19-Aug-05	7	South	N402F	7873	4.02	664	7.2	18	80 95	
	7	Pour missed due to a hasty change in construction timing without research notification								

Refer to order number P104257 or job number 62 for more details.

Details of concrete pour absent

2 litres/m³ of accelerator added (dataset AF, from Grace) which only affects v v early strength gain I.e. <5hours

**Details of concrete supplied to the construction site of 151 Pirie
for the partially prestressed suspended slabs.**

DateCast	Truck	LoadSize (m3)	Location	Time		Temp (deg C)		Slump (mm)	
				Batched	Sampled	Conc	Air	Design	Measured
11/5/2005	8664	7.2	Level 1 Pour 1	4:20 AM	5:00 AM	21	9	80	75
11/5/2005	8664	7.2	Level 1 Pour 1	4:20 AM	5:00 AM	21	9	80	75
11/5/2005	8664	7.2	Level 1 Pour 1	4:20 AM	5:00 AM	21	9	80	75
11/5/2005	8662	5.8	Level 1 Pour 1	4:58 AM	5:25 AM	21	10	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	4:58 AM	5:25 AM	21	10	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	4:58 AM	5:25 AM	21	10	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	6:05 AM	6:45 AM	20	12	80	95
11/5/2005	8662	5.8	Level 1 Pour 1	6:05 AM	6:45 AM	20	12	80	95
11/5/2005	8662	5.8	Level 1 Pour 1	6:05 AM	6:45 AM	20	12	80	95
11/5/2005	8656	5.8	Level 1 Pour 1	6:38 AM	7:15 AM	20	12	80	80
11/5/2005	8656	5.8	Level 1 Pour 1	6:38 AM	7:15 AM	20	12	80	80
11/5/2005	8656	5.8	Level 1 Pour 1	6:38 AM	7:15 AM	20	12	80	80
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
11/5/2005	8662	5.8	Level 1 Pour 1	7:06 AM	7:50 AM	20	12	80	85
20/05/2005	8688	7.2	Level 1 Pour 2	4:33 AM	5:10 AM	18	15	80	70
20/05/2005	8688	7.2	Level 1 Pour 2	4:33 AM	5:10 AM	18	15	80	70
20/05/2005	8688	7.2	Level 1 Pour 2	4:33 AM	5:10 AM	18	15	80	70
20/05/2005	8672	10	Level 1 Pour 2	5:16 AM	5:55 AM	18	16	80	100
20/05/2005	8672	10	Level 1 Pour 2	5:16 AM	5:55 AM	18	16	80	100
20/05/2005	8672	10	Level 1 Pour 2	5:16 AM	5:55 AM	18	16	80	100
20/05/2005	8687	7.2	Level 1 Pour 2	5:57 AM	7:30 AM	19	15	80	90
20/05/2005	8687	7.2	Level 1 Pour 2	5:57 AM	7:30 AM	19	15	80	90
20/05/2005	8687	7.2	Level 1 Pour 2	5:57 AM	7:30 AM	19	15	80	90
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8607	5.8	Level 1 Pour 2	7:07 AM	8:05 AM	18	15	80	70
20/05/2005	8662	5.8	Level 1 Pour 2	5:25 AM	6:35 AM	18	15	80	85
20/05/2005	8662	5.8	Level 1 Pour 2	5:25 AM	6:35 AM	18	15	80	85
20/05/2005	8662	5.8	Level 1 Pour 2	5:25 AM	6:35 AM	18	15	80	85
30/05/2005	8691	5.8	Level 2 Pour 1	4:28 AM	5:15 AM	16	9	80	80
30/05/2005	8691	5.8	Level 2 Pour 1	4:28 AM	5:15 AM	16	9	80	80
30/05/2005	8691	5.8	Level 2 Pour 1	4:28 AM	5:15 AM	16	9	80	80
30/05/2005	8653	5.8	Level 2 Pour 1	4:57 AM	6:05 AM	16	8	80	80
30/05/2005	8653	5.8	Level 2 Pour 1	4:57 AM	6:05 AM	16	8	80	80
30/05/2005	8653	5.8	Level 2 Pour 1	4:57 AM	6:05 AM	16	8	80	80

22/07/2005	8486	7.2	Level 5 Pour 1	5:11 AM	6:05 AM	15	13	80	85
22/07/2005	8486	7.2	Level 5 Pour 1	5:11 AM	6:05 AM	15	13	80	85
22/07/2005	8486	7.2	Level 5 Pour 1	5:11 AM	6:05 AM	15	13	80	85
27/07/2005	8663	5.6	Level 5 Pour 2	data not aquired		21	15	80	90
27/07/2005	8663	5.6	Level 5 Pour 2	from concrete supplier		21	15	80	90
27/07/2005	8663	5.6	Level 5 Pour 2			21	15	80	90
27/07/2005	8663	5.6	Level 5 Pour 2			21	15	80	90
27/07/2005	8663	5.6	Level 5 Pour 2			21	15	80	90
27/07/2005	8663	5.6	Level 5 Pour 2			21	15	80	90
27/07/2005	8663	5.6	Level 5 Pour 2			21	15	80	90
27/07/2005	8668	7.2	Level 5 Pour 2			16	9	80	85
27/07/2005	8668	7.2	Level 5 Pour 2			16	9	80	85
27/07/2005	8668	7.2	Level 5 Pour 2			16	9	80	85
27/07/2005	8664	7.2	Level 5 Pour 2			18	12	80	80
27/07/2005	8664	7.2	Level 5 Pour 2			18	12	80	80
27/07/2005	8664	7.2	Level 5 Pour 2			18	12	80	80
27/07/2005	8691	5.6	Level 5 Pour 2			18	13	80	90
27/07/2005	8691	5.6	Level 5 Pour 2			18	13	80	90
27/07/2005	8691	5.6	Level 5 Pour 2			18	13	80	90
8/5/2005	8668	7.2	Level 6 Pour 1	data not aquired		17	8	80	95
8/5/2005	8663	5.6	Level 6 Pour 1	from concrete supplier		17	8	80	95
8/5/2005	8663	5.6	Level 6 Pour 1			17	8	80	95
8/5/2005	8663	5.6	Level 6 Pour 1			17	8	80	95
8/5/2005	8663	5.6	Level 6 Pour 1			17	8	80	95
8/5/2005	8663	5.6	Level 6 Pour 1			17	8	80	95
8/5/2005	8663	5.6	Level 6 Pour 1			17	8	80	95
8/5/2005	8663	5.6	Level 6 Pour 1			17	8	80	95
8/5/2005	8684	7.2	Level 6 Pour 1			17	8	80	95
8/5/2005	8684	7.2	Level 6 Pour 1			17	8	80	95
8/5/2005	8684	7.2	Level 6 Pour 1			15	10	80	95
8/5/2005	8664	7.2	Level 6 Pour 1			15	10	80	95
8/5/2005	8664	7.2	Level 6 Pour 1			15	10	80	95
8/5/2005	8664	7.2	Level 6 Pour 1			16	7	80	85
8/5/2005	8465	7.2	Level 6 Pour 1			16	7	80	85
8/5/2005	8465	7.2	Level 6 Pour 1			16	7	80	85
8/5/2005	8465	7.2	Level 6 Pour 1			16	8	80	80
8/5/2005	8465	7.2	Level 6 Pour 1			16	8	80	80
8/5/2005	8465	7.2	Level 6 Pour 1			16	8	80	80
8/10/2005	8691	5.6	Level 6 Pour 2	2:33 AM	3:30 AM	15	10	80	90
8/10/2005	8691	5.6	Level 6 Pour 2	2:33 AM	3:30 AM	15	10	80	90
8/10/2005	8691	5.6	Level 6 Pour 2	2:33 AM	3:30 AM	15	10	80	90
8/10/2005	8684	7.2	Level 6 Pour 2	3:35 AM	4:35 AM	15	9	80	90
8/10/2005	8684	7.2	Level 6 Pour 2	3:35 AM	4:35 AM	15	9	80	90
8/10/2005	8684	7.2	Level 6 Pour 2	3:35 AM	4:35 AM	15	9	80	90
8/10/2005	8689	6.8	Level 6 Pour 2	5:23 AM	6:30 AM	15	10	80	95
8/10/2005	8689	6.8	Level 6 Pour 2	5:23 AM	6:30 AM	15	10	80	95
8/10/2005	8689	6.8	Level 6 Pour 2	5:23 AM	6:30 AM	15	10	80	95
8/10/2005	8486	7.2	Level 6 Pour 2	6:17 AM	7:20 AM	15	8	80	95
8/10/2005	8486	7.2	Level 6 Pour 2	6:17 AM	7:20 AM	15	8	80	95
8/10/2005	8486	7.2	Level 6 Pour 2	6:17 AM	7:20 AM	15	8	80	95
8/10/2005	8486	7.2	Level 6 Pour 2	6:17 AM	7:20 AM	15	8	80	95
8/10/2005	8486	7.2	Level 6 Pour 2	6:17 AM	7:20 AM	15	8	80	95
8/10/2005	8486	7.2	Level 6 Pour 2	6:17 AM	7:20 AM	15	8	80	95
8/10/2005	8486	7.2	Level 6 Pour 2	6:17 AM	7:20 AM	15	8	80	95
19/08/2005	8684	7.2	Level 7 Pour 1	3:23 AM	3:45 AM	18	14	80	95
19/08/2005	8684	7.2	Level 7 Pour 1	3:23 AM	3:45 AM	18	14	80	95

APPENDIX E


Concrete Compressive Strength (f_c) Results from the Experimental Analysis.

First Floor SOUTH Slab

Strength records

SITE CURED				
Compressive strength (MPa)				
Day	# 1	# 2	# 3	Average
3	15.9	16.9	14	15.6
7	22.97	23.04	23.34	23.1
14	27.57	27.78	26.09	27.14667
28	29.43	30.57	-	30
56	35.66	34.89	-	35.275

LAB CURED				
Compressive strength (MPa)				
Day	# 1	# 2	# 3	Average
3	16.8	14	-	15.4
7	24.53	25.54	-	25.035
14	30.05	31.13	32.4	31.19333
28	38.46	38.73	35.57	37.58667



First Floor NORTH Slab

Strength of 1 day samples

6.4 MPa

9.2 MPa

Average


7.8 MPa

SITE CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	13.57	14.2	16.78	14.85
7	19.2	20.5	20.37	20.02333
14	25.36	22.47	23.97	23.93333
28	26.5	25.46	25.06	25.67333

LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	20.92	20.32	18.1	19.78
7	24.02	26.11	26.17	25.43333
14	30.6	29.14	26.71	28.81667
28	34.99	30.85	37.54	34.46



Second Floor SOUTH Slab

Strength of 1 day samples

8.99 MPa

9.88 MPa


Average 9.435 MPa

SITE CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	16.73	16.26	16.37	16.45
7	22.59	22.01		22.3
15	26	24.86		25.43
29	27.59	28.67		28.13

LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	20.57	19.48	19.61	19.89
7	27.02	28.14	26.14	27.58
15	31.19	31.18	30.07	30.81
29	38.75	39.78	39.56	39.36



Second Floor NORTH Slab

Strength of 1 day samples

9.32 MPa
10.16 MPa
9.74 MPa


Average

SITE CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	15.58	15.83	15.9	15.77
8	18.96	20.7	19.83	19.8
14	21.24	22.45	21.32	21.67
28	23.68	28.24	-	25.96

LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	18.38	17.75	18.83	18.32
8	24.71	25.44	23.77	25.075
14	29.51	28.07	29.71	29.09667
28	34.75	33.83	-	34.29



Third Floor SOUTH Slab

Strength of 1 day samples

8.29 MPa

8.7 MPa


Average 8.495 MPa

SITE CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	17.92	16.79	18.42	17.71
7	26	23.12	25.61	24.9
14	29.47	29.41	-	29.44
28	28.15	23.09	-	25.62

LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	24.36	22.23	24.19	23.59333
7	32.4	31.95	33.06	32.175
14	35.75	37.87	-	36.81
28	34.01	37.54	-	35.775



Third Floor NORTH Slab

Strength of 2 day samples

11.95 MPa

- MPa

Average


11.95 MPa

SITE CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	15.57			15.57
7	19.78	19.97	-	19.9
14	24.02	21.9		22.96
28				
60	35.09			35.09

LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
	N/A	N/A	N/A	#DIV/0!
7	23.59	27.81	-	25.7
14	28.34	29.17		28.755
28				
60				



Fourth Floor NORTH Slab

Strength of 2 day samples

10.15 MPa

8.67 MPa

Average


9.41 MPa

SITE CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	17.12	18.59		17.855
7	29.82	30.1		30.0
14	34.67	36.3		35.485
29	34.41	32.98	31.35	32.91333

LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3	18.97	21.57		20.27
7	37.51	33.92		35.715
14	43.61	43.23		43.42
29	49.22	39.14	45.31	44.55667



Fifth Floor SOUTH Slab


SITE CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3				
7	26.69	26.67		26.68
15	27.67	29.4		28.535
29	32.57	30.55		31.56

LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
3				
7	30.43	28.52		29.475
15	29.62	39.62		39.62
29	40.25	40.66		40.455

recorded but not included due to bad shear failure and compress stress value is significantly less than the next cylinder tested.



Seventh Floor SOUTH Slab


Strength of 1 day samples 10.37 MPa
10.85 MPa
Average 10.61 MPa

SITE CURED



Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
4	20.53	18.69		19.61
7	25.46	25.36		25.41
17	27.65	25.87		26.76
28				


LAB CURED

Day	Compressive strength (MPa)			Average
	# 1	# 2	# 3	
4	25.34	27.28		26.31
7	30.27	29.6		29.935
17	34.85	33.43		34.14
28				




The following figures are detailed photos taken of the premature failure that was occurring when testing for compressive strength with the rubber caps at early ages.







The next set of figures show detail about the cylinder labelled as "2SL3". Which is sampled from the 2nd floor, south side slab pour and is the 3rd cylinder which is laboratory cured. This cylinder was dropped from the preparation table. The only damage to the cylinder is to the top corner, which is shown in the pictures. Due to the clean failure, displayed, the recorded compressive stress was included in the experimental data set.



Damage can be seen at the leading top edge.




Crack propagation at failure, shown on the front and back of the test cylinder.

APPENDIX F


Concrete Modulus of Elasticity (E_c) Results from the Experimental Analysis.



The following data is an example of how the value of E_c was determined for the test cylinders taken from 151 Pirie.

DATA SET
1st floor slab
North Pour
Day 3
Site cured



The three separate loading lines are then analysed separately. A trendline is applied to the three separate loading lines. The following three graphs are an example of this -





The average value of E_c is then determined from an average of the three separate loadings.

Mod of E values	
1	23601 MPa
2	23475 MPa
3	23275 MPa
Average	23450.33 MPa

Electronic copies of each E_c test have been recorded and are available in the Experimental Data folder.


1st Floor Slab, South Pour

SITE CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	24782	24987	25154	24974.33
7	28982	28250	28657	28629.67
7	29605	29371	29107	29361
14	31086	30526	31056	30889.33
28	32381	32001	32101	32161
56	33563	33352	33827	33580.67

LAB CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	28731	28758	28969	28819.33
7	31732	31663	32389	31928
14	36519	36059	35534	36037.33
28	37503	37723	37827	37684.33




1st Floor Slab, North Pour

1day sample	19486 MPa
	19896 MPa
	20426 MPa
Average	19936 MPa

SITE CURED				
Modulus of Elasticity (MPa)				
Day	# 1	# 2	# 3	Average
3	23601	23475	23275	23450.33
3	23375	23480	24290	23715
7	23721	24110	24291	24040.67
14	30624	30825	30145	30531.33
28	26588	26489	27024	26700.33

Potential inaccuracy

LAB CURED				
Modulus of Elasticity (MPa)				
Day	# 1	# 2	# 3	Average
3	29232	29336	29704	29424
7	31399	30935	30765	31033
14	33839	33840	33462	33713.67
28	36788	36997	37164	36983




2nd Floor Slab, South Pour

SITE CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	24179	24489	23915	24194.33
7	26874	26731	26478	26694.33
15	27533	27856		27694.5
29	31546	31498	31375	31473

LAB CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	24318	24219	24018	24185
7	28038	27847	28087	27990.67
15	31178	31346		31262
29	36861	38141	38164	37722



2nd Floor Slab, North Pour


1day sample	18414 MPa
	17410 MPa
	17267 MPa
Average	17697 MPa

SITE CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	21017	20432	21092	20847
8	22506	22447	22119	22357.33
14	24046	24154	24249	24149.67
28	25067	24822	24546	24811.67

LAB CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	24122	23569	23274	23655
8	24596	24693	25075	24788
14	27145	27228	27264	27212.33
28	30376	30525	30434	30445



3rd Floor Slab, South Pour


1day sample	19756	MPa
	19803	MPa
	19496	MPa
Average	19685	MPa

SITE CURED				
Modulus of Elasticity (MPa)				
Day	# 1	# 2	# 3	Average
3	22160	22887	22731	22592.67
7	40051	39069	38405	39175
14	27259	27136	26680	27025
28	28809	28920	28639	28789.33


LAB CURED				
Modulus of Elasticity (MPa)				
Day	# 1	# 2	# 3	Average
3	24827	25170	25218	25071.67
7	31568	31617	31721	31635.33
14	31568	31617	31721	31635.33
28	32575	32555	33030	32720

**THIS POINT IS REMOVED
ASSUMED EXPERIMENTAL ERROR**

INITIAL GRAPH



ADJUSTED GRAPH



3rd Floor Slab, North Pour

2 day sample	23942 MPa
	23714 MPa
	24188 MPa
Average	23948 MPa


SITE CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
7	N/A	N/A	N/A	#DIV/0!
14	23609	24288	22408	23435
60	21450	21465	21341	21418.67
	23381	23453	23190	23341.33

This data may need to be ignored as the cylinder that was tested failed prematurely (possibly damaged on site)

LAB CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
7	30264	29367	30001	29877.33
14	27540	27315	27266	27373.67



4th Floor Slab, South Pour

1day sample 16801 MPa
 17062 MPa
 17214 MPa


 Average 17025.67 MPa

SITE CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	24807	25048	25186	25013.67
7	27392	27327	27185	27301.33
14	30196	30297	30196	30229.67
28	35095	35034	34985	35038

LAB CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	30165	30353	29522	30013.33
7	32517	32701	32732	32650
14	34588	34841	35028	34819
28	38551	38710	38616	38625.67



4th Floor Slab, North Pour


1day sample	13506	MPa
	13436	MPa
	13364	MPa
Average		13435.33 MPa

SITE CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	29834	30024	29526	29794.67
7	31128	31460	31317	31301.67
14	33529	33726	33934	33729.67
29				

LAB CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3	31049	31114	31086	31083
7	36779	36967	36781	36842.33
14	38852	38947	38694	38831
29				




5th Floor Slab, South Pour

SITE CURED				
Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3				
7				
15				
29	32954	33244	32996	33064.67
29DT	34795	34483	34230	34502.67

This data is the E_c data obtained from a cylinder cured on site at the same elevation as the curing slab. This was performed to determine if there is a difference between site cured on the ground and at the same height as the suspended slab

LAB CURED				
Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
3				
7	35062	35263	35108	35144.33
15	39443	39664	39602	39569.67
29	41061	41272	41457	41263.33



6th Floor Slab, North Pour


1day sample	21007	MPa
	20913	MPa
	21338	MPa
Average	21086	MPa

SITE CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
5	29424	29178	29196	29266
7	29455	29668	29611	29578
14	35142	35704	35294	35380
29	34999	35473	35205	35225.67

LAB CURED

Day	Modulus of Elasticity (MPa)			Average
	# 1	# 2	# 3	
5	35530	36361	35982	35957.67
7	36232	36424	36482	36379.33
14	36681	37193	37174	37016
29	40537	40619	41156	40770.67




7th Floor Slab, South Pour

1day sample	19518	MPa	
	19731	MPa	
	19755	MPa	
Average	19668	MPa	

SITE CURED				
Modulus of Elasticity (MPa)				
Day	# 1	# 2	# 3	Average
4				
7				
17	32313	32654	32514	32493.67
28				

LAB CURED				
Modulus of Elasticity (MPa)				
Day	# 1	# 2	# 3	Average
4	30669	30545	30751	30655
7				
17	36397	36600	36629	36542
28				



4025
3rd Floor
North
7 days.

2/7/05

YOUNGS MODULUS TEST

156
159.4
126.4
220.6

Load (KN)	Deflection (Div.)								
	Group 3N55			Group 3NLS			Group 3		
	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3
0	0	0	0	0	0	0			
10	3	3.8	3.1	3.2 3.2	2.4	2.0			
20	9.5	9.3	8.94 8.4	8.6 7.9	7.0	6.4			
30	13.9	17.8	16.9	11.9	11.8	10.6			
40	21.8	22.3	23.5	18.3	18.5	17.2			
50	29.3	29.6	31.9	23.5	23.2	21.9			
60	38.1	38.1	39.2	29.9	29.8	28.6			
70				35.7	36.1	34.9			

Note:

Gauge length = ~~130~~ 132 mm

Conversion: 1 Div. = 0.002 mm

28/6/05

$F = \sigma a$
 $\sigma = \frac{F}{A}$


YOUNGS MODULUS TEST

Load (KN)	Deflection (Div.)											
	Group MD. 2 - 40kN			Group 2SS11 - 80kN			Group 3 2SL12 - 120kN					
	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3
5	1/4	1	1	10	4	3	2.5	10	3	2	2	
10	3	4	4	20	7	6	7	20	6	5	6	
15	6	6	7	30	12.5	12	13	30	11	9	9	
20	9	9	10	40	18	17 17	17	40	15	13	14	
25	13	13	14	50	22	23	22.5	50	20	17	18	
30	17	17.5	18	60	29	28	28	60	25	21	22	
35	21	22	21.5	70	34	34	34	70	29	27	27	
				80	40.5	39	40	80	38 38	30.5	31	
								90	38	36	36	
								100	43	40	41	
								110	47	45	46	
								120	52	48	48	

Note:

Gauge length = ~~130~~¹³² mm

Conversion: 1 Div. = 0.002 mm remember to $\div 2$.



YOUNGS MODULUS TEST

1/7/05

Load (KN)	Deflection (Div.)								
	Group 3528			Group 3558			Group 3		
	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3
10	1	1	2	3	3	3			
20	5	5	5	8	8	9			
30	9	9	10	15	14	14			
40	15	14	16	19	21	20			
50	20	20	21	26	27	28			
60	25	25	25	32	32	33			
70	30	30	32	38	39	39			
80	37	36	37	45	45	46			
90	41	42	43	51	51	52			
100	47	46	47						
110 Note:	52	52	52						

Gauge length = 130¹³² mm

Conversion: 1 Div. = 0.002 mm

